

Term & Conditions for the bidders.

Please read carefully the term and conditions before applying.

Instructions for Bidders.

1. Must be a registered firm with Government and FBR (Please attach copy of business Registration, NTN certificates).
2. Profile of the Firm with last 03 Years Experiences in WASH Sector with past 3 years Tax Returns files with Valid CNIC of the Owner/directors of the company.
3. Please attach last 06 Months bank statement of the Firm showing the financial strength.
4. Please attach bank soundness certificate of the firm.
5. Reference letters / Certificates showing the similar past experience with valid contact numbers.
6. No quotation will be acceptable for in-complete items in a specific kit.
7. All bids may be quoted on the basis of Unit Rate/item wise.
8. No mistake will be allowed in Unit Rate, in case of cutting and over writing the bidder should sign against the error with Stamp/Seal.
9. No requests for increasing unit rates will be entertained once the sealed bidding documents gets opened.
10. All interested vendors will be called for a meeting where WASH Engineer will brief the nature of work to the vendors and will answer the queries or confusions in the documents. The vendors should ensure their presence by 11:30 PM on 18 July 2020 at Muslim Hands Regional Office, House No 48, New Al-Gilani Street, Zarghoon Road, Quetta Balochistan.
11. The Validity of the Quotation will be 60 days.
12. All the bids must contain the Date, legal name and address.
13. All bids must contain the earnest money @ 5% of the total bid in the shape of CDR/Bank Draft. Which will be returned either on rejection of bid / or (in case of awarding of tender), at the time of payment.
14. All bidders need to send two envelopes by courier, one for Technical Bid and 2nd for financial bid.
15. The quotation must include all applicable taxes which must be mentioned separately and if not mentioned than it will be considered including taxes.
16. Interested firms submit their bids in sealed envelopes in the name of "Procurement Committee Muslim Hands", and the envelopes must mark as "Technical Bid" and "Financial Bid" applied for, not later than 22 July 2020 before 1400 hrs. The tenders will be opened on the same day.

Performance of the contract.

The performance of the contract will be in District Ziarat, at sites UC Ziarat and UC Kaza & Chowtair of Tehsil Sanjavi as suggested in tender documents or as agreed upon.

Payment Method.

The payment will be made within 02 weeks (after deduction of all applicable taxes) after the Completion of all agreed work and having verification / Certificate of completion issued by the Engineer WASH.

Short listing.

The procurement committee will short list the bids on the basis of Earliest Completion of the Work, Lowest Bidder, Quality of Material, and Technical Evaluation of the vendor which will be communicated to the selected bidders in due course of time. Earliest Possible Work Completion will be counted and considered while bid analyses.

NOTE. The Organization reserves the right to reject, cancel, negotiate, accept any offer without assigning any reason and without considering the lowest rate, or may divide one item/kit among more than 01 vendors. Detail BOQ and specifications are mentioned below. In case of any query related to specifications / nature of work etc. Please contact at **(Muslim Hands Regional Office, House # 48, New Algilani street,Zarghoon Road Quetta** or contact at **081-2869167** (hashim_mhi@yahoo.com).

1. Killi Sardaran, Ziarat

Type of Scheme: Rehabilitation of Drinking Water Facilities **Project:** Emergency Response for Snowfall/Flood Affectees at ziarat Balochistan

S.No	Description	Quoted Amount			
	1) Labour	Quantity/Nos	Unit	Unit Cost	Amount
1	A) Skilled Labour	13	MD		
2	B. Unskilled	43	MD		
3	C. Plumber	1	Job		
Sub Total (Labour)					
	2) Materials				
1	Cement	12	No		
2	Sand	45	Cft		
3	Crash	55	Cft		
5	G.I Pipes 2"	7	Rft		
6	G.I Pipe 1.5"	10	Rft		
7	Transportation	1	Job		
8	Accessories (Fittings, cutting, jointi	1	Job		
9	Existing Water Tank Repair	1	Job		
10	G.I Bib Cock	10	No		
12	Sign Board	1	No		
Sub Total (Material)					
	3) Pumping Machinery				
1	Solar Panel 350 Watt A Grade Poly Crysteline	6	No		
2	HP,Submersible Pump 2 Hp Three Phase (Dongyin or equivalent) as per	1	No		
3	Inveter 3 Kw (Invt China) for Submersible	1	No		
4	Solar Mounting Frame Fixed	6	No		
5	Ac 4 Core Cable 4mm	50	Rft		
5	7/29 Cable For Panel Conections	50	Rft		
6	Safty Robe	15	Rft		
8	1.5" Dia PE Pipe PN12 (from Solar to Tank)	1500	Rft		
9	Acceseries (Fittings, Nuts & Bolts)	1	Job		
10	Installation and comisioning Charges	1	Job		
11	Transportation	1	Job		
Sub Total (Pumping Machinery)					
Grand Total (1+2+3) (All taxes should be included in unit rates)					

Contractor Sign & Seal

2- Baerh Chawtra, Ziarat

Type of Scheme: Rehabilitation of Drinking Water Facilities **Project:** Emergency Response for Snowfall/Flood Affectees at ziarat Balochistan

S.No	Description	Total Estimated Cost (Rs.)			
1) Labour		Quantity/Nos	Unit	Unit Cost	Cost (Rs)
1	A) Skilled Labour	5	MD		
2	B. Unskilled	21	MD		
3	C. Plumber	1	Job		
Sub Total (Labour)					
2) Materials					
1	Cement	24	No		
2	Sand	82	Cft		
3	Crash	164	Cft		
4	HDPE Pipe 0.75"	2000	Rft		
5	G.I Pipes 2"	21	Rft		
6	G.I Pipe 1.5"	30	Rft		
7	Transportation	1	Job		
8	Accessories (Fittings, cutting, jointing, Couplers, Sockets, Elbows as required etc)	1	Job		
9	Water tank Jasti	1	Job		
10	G.I Bib Cock	15	No		
11	Sign Board	1	No		
Sub Total (Material)					
3) Pumping Machinery					
1	Solar Panel 350 Watt A Grade Poly Crysteline	6	No		
2	HP,Submersible Pump 1.5 Hp Three Phase as per approval of Engineer In-	1	No		
3	Inveter 2 Kw (Invt China) for Submersible	1	No		
4	Solar Mounting Frame Fixed	6	No		
5	Ac 4 Core Cable 4mm	50	Rft		
5	7/29 Cable For Panel Conections	50	Rft		
6	Safy Robe	10	Rft		
8	1" Dia PE Pipe PN12 (from Solar to Ground)	1600	Rft		
9	Acceseries (Fittings, Nuts & Bolts)	1	Job		
10	Installation and comisioning Charges	1	Job		
11	Transportation	1	Job		
Sub Total (Pumping Machinery)					
Grand Total (1+2+3) (Inclusive of all taxes)					

Contractor Sign & Seal

3- Gulzar Manan, Ziarat

Type of Scheme: Rehabilitation of Drinking Water Facilities **Project:** Emergency Response for Snowfall/Flood Affectees at ziarat Balochistan

S.No	Description	Total Estimated Cost (Rs.)			
	1) Labour	Quantity/Nos	Unit	Unit Cost	Cost (Rs)
1	A) Skilled Labour	2	MD		
2	B. Unskilled	8	MD		
3	C. Plumber	1	Job		
Sub Total (Labour)					
	2) Materials				
1	Cement	8	No		
2	Sand	27	Cft		
3	Crash	55	Cft		
3	HDPE Pipe 2.5"	1650	Cft		
4	G.I Pipes 2"	10	Rft		
5	G.I Pipe 1.5"	10	Rft		
6	Transportation	1	Job		
7	Accessories (Fittings, cutting, jointi	1	Job		
8	Water tank Repair	1	Job		
9	G.I Bib Cock	15	No		
11	Sign Board	1	No		
Sub Total (Material)					
Grand Total (1+2)					

Contractor Sign & Seal

4- Zar Channa, Ziarat

Type of Scheme: Rehabilitation of Drinking Water Facilities **Project:** Emergency Response for Snowfall/Flood Affectees at ziarat Balochistan

S.No	Description	Total Estimated Cost (Rs.)			
		Quantity/Nos	Unit	Unit Cost	Cost (Rs)
1) Labour					
1	A) Skilled Labour	3	MD		
2	B. Unskilled	18	MD		
3	C. Plumber	1	Job		
Sub Total (Labour)					
2) Materials					
1	Cement	16	No		
2	Sand	55	Cft		
3	Crash	110	Cft		
4	G.I Pipes 2"	10	Rft		
5	G.I Pipe 1.5"	10	Rft		
6	Transportation	1	Job		
7	Accessories (Fittings, cutting, joint)	1	Job		
8	Water Tank Repair with RCC Slab 1:2:4	1	Job		
9	G.I Bib Cock	15	No		
10	HDPE 2" Pipe PN-12	5000	Job		
11	Sign Board	1	No		
Sub Total (Material)					
Grand Total (1+2)					

Contractor Sign & Seal

5- Malikat Shin Maghzai

Type of Scheme: Rehabilitation of Drinking Water Facilities **Project:** Emergency Response for Snowfall/Flood Affectees at ziarat Balochistan

S.No	Description	Total Estimated Cost (Rs.)			
		Quantity/Nos	Unit	Unit Cost	Cost (Rs)
1) Labour					
1	A) Skilled Labour	4	MD		
2	B. Unskilled	11	MD		
3	C. Plumber	1	Job		
Sub Total (Labour)					
2) Materials					
	Well Digging & Cleaning upto 5m	1	Job		
1	Cement	10	No		
2	Bricks	413	No		
3	Sand	44	Cft		
4	Crash	55	Cft		
5	HDPE Pipe 1.5"	1500	Rft		
6	G.I Pipes 2"	7	Rft		
7	G.I Pipe 1.5"	10	Rft		
8	Transportation	1	Job		
9	Accessories (Fittings, cutting, Hand	1	Job		
10	Jasti Chadar Water Tank (8'x4'x4')	1	Job		
11	G.I Bib Cock	10	No		
12	Sign Board	1	No		
Sub Total (Material)					
3) Pumping machinery					
1	Solar Panel 350 Watt A Grade Poly Crysteline	6	No		
2	HP,Submersible Pump 1.5 Hp Three Phase (Dongyin or equivalent) as per	1	No		
3	Inveter 3 Kw (Invt China) for Submersible	1	No		
4	Solar Mounting Frame Fixed	6	No		
5	Ac 4 Core Cable 4mm	50	Rft		
5	7/29 Cable For Panel Conections	50	Rft		
6	Safty Robe	30	Rft		
9	Acceseries (Fittings, Nuts & Bolts)	1	Job		
10	Installation and comisioning Charges	1	Job		
11	Transportation	1	Job		
Sub Total (Material)					
Grand Total (1+2+3)					

6- Shadi Ghat, Ziarat

Type of Scheme: Rehabilitation of Drinking Water Facilities **Project:** Emergency Response for Snowfall/Flood Affectees at ziarat Balochistan

S.No	Description	Total Quoted Cost (Rs.)			
	1) Labour	Quantity/Nos	Unit	Unit Cost	Cost (Rs)
1	A) Skilled Labour	2	MD		
2	B. Unskilled	8	MD		
3	C. Plumber	1	Job		
Sub Total (Labour)					
	2) Materials				
1	Cement	11	No		
2	Sand	35	Cft		
3	Crash	71	Cft		
3	HDPE Pipe 3"	1000	Cft		
4	G.I Pipes 2"	10	Rft		
5	G.I Pipe 1.5"	10	Rft		
6	Transportation	1	Job		
7	Accessories (Fittings, cutting, jointi	1	Job		
8	Water Tank	1	Job		
9	G.I Bib Cock	15	No		
10	Pumping Machinery	1	Job		
11	Sign Board	1	No		
Sub Total (Material)					
	3) Pumping Machinery				
1	Electric 3Phase Submersible Motor 10HP with SP46-6 Nos Router as per approval of Engineer In-Charge	1	No		
2	Ac 3 Core Cable 25mm	70	Rft		
3	Safty (Rope)	50	Rft		
4	Panel Board with Breakers	1	Job		
5	Accesseries (Fittings, Nuts & Bolts, Gate Valve, Cleag Pipes with Girder Support)	1	Job		
6	Installation and comisioning Charges	1	Job		
7	Transportation	1	Job		
Sub Total (Pumping Machinery)					
Grand Total (1+2+3)					

Contractor Sign & Seal

7-Chawtra, Ziarat

Type of Scheme: Rehabilitation of Drinking Water Facilities **Project:** Emergency Response for Snowfall/Flood Affectees at Ziarat Balochistan

S.No	Description	Total Quoted Cost (Rs.)			
	1) Labour	Quantity/Nos	Unit	Unit Cost	Cost (Rs)
1	A) Skilled Labour	5	MD		
2	B. Unskilled	18	MD		
3	C. Plumber	1	Job		
Sub Total (Labour)					
	2) Materials				
1	Cement	24	No		
2	Sand	82	Cft		
3	Crash	164	Cft		
4	HDPE Pipe 0.75"	600	Rft		
5	G.I Pipes 2"	21	Rft		
6	G.I Pipe 1.5"	30	Rft		
7	Transportation	1	Job		
8	Accessories (Fittings, cutting, joint)	1	Job		
9	Water tank Jasti	1	Job		
10	G.I Bib Cock	15	No		
11	Sign Board	1	No		
Sub Total (Material)					
	3) Pumping Machinery				
1	Solar Panel 350 Watt A Grade Poly Crysteline	8	No		
2	HP,Submersible Pump 2 Hp Three Phase as per approval of Engineer In-	1	No		
3	Inveter 3 Kw (Invt China) for Submersible	1	No		
4	Solar Mounting Frame Fixed	8	No		
5	Ac 4 Core Cable 4mm	100	Rft		
5	7/29 Cable For Panel Conections	150	Rft		
6	Safty Robe	10	Rft		
8	1" Dia PE Pipe PN12 (from Solar to Ground)	2500	Rft		
9	Acceseries (Fittings, Nuts & Bolts)	1	Job		
10	Installation and comisioning Charges	1	Job		
11	Transportation	1	Job		
Sub Total (Pumping Machinery)					
Grand Total (1+2+3)					

Contractor Sign & Seal

8-Wocha Ghoski, Ziarat

Type of Scheme: Rehabilitation of Drinking Water Facilities **Project:** Emergency Response for Snowfall/Flood Affectees at Ziarat Balochistan

S.No	Description	Total Quoted Cost (Rs.)			
1) Labour		Quantity/Nos	Unit	Unit Cost	Cost (Rs)
1	A) Skilled Labour	3	MD		
2	B. Unskilled	27	MD		
3	C. Plumber	1	Job		
Sub Total (Labour)					
2) Materials					
1	Digging & Cleaning of Well Upto 3m)	1	Job		
2	Cement	14	No		
3	Sand	46	Cft		
4	Crash	91	Cft		
5	G.I Pipes 2"	11	Rft		
6	G.I Pipe 1.5"	10	Rft		
7	Transportation	1	Job		
8	Accessories (Fittings, cutting, jointi	1	Job		
9	Jasti Chadar Water Tank	1	Job		
10	G.I Bib Cock	10	No		
11	Solar System Complete	1	Job		
12	Sign Board	1	No		
Sub Total (Material)					
3) Pumping Machinery					
1	Solar Panel 350 Watt A Grade Poly Crysteline	4	No		
2	Submersible Motor 1 HP, Submersible Pump 1 Hp Three Phase as per approval of Engineer In-Charge	1	No		
3	Inveter 1 Kw (Invt China) for Submersible	1	No		
4	Solar Mounting Frame Fixed	4	No		
5	Ac 4 Core Cable 4mm	70	Rft		
5	7/29 Cable For Panel Conections	50	Rft		
6	Safy Robe	15	Rft		
8	1" Dia PE Pipe PN12 (from Solar to Ground)	1000	Rft		
9	Acceseries (Fittings, Nuts & Bolts)	1	Job		
10	Installation and comisioning Charges	1	Job		
11	Transportation	1	Job		
Sub Total (Pumping Machinery)					
Grand Total (1+2+3)					

Contractor Sign & Seal

9-Badhi Gharh

Type of Scheme: Rehabilitation of Drinking Water Facilities **Project:** Emergency Response for Snowfall/Flood Affectees at ziarat Balochistan

S.No	Description	Total Estimated Cost (Rs.)			
		Quantity/Nos	Unit	Unit Cost	Cost (Rs)
1) Labour					
1	A) Skilled Labour	3	MD		
2	B. Unskilled	6	MD		
3	C. Plumber	1	Job		
Sub Total (Labour)					
2) Materials					
1	Well Cleaning 5m	1	Job		
2	Cement	15	No		
3	Sand	45	Cft		
4	Crash	90	Cft		
5	G.I Pipes 2"	10	Rft		
6	G.I Pipe 1.5"	10	Rft		
7	Transportation	1	Job		
8	Accessories (Fittings, cutting, jointi	1	Job		
9	Steel Bars for Well Cover	250	Kg		
10	Water Tank Jasti (8'x8'x4')	1	Job		
12	G.I Bib Cock	15	No		
13	Sign Board	1	No		
Sub Total (Material)					
3) Pumping Machinery					
1	Solar Panel 350 Watt A Grade Poly Crysteline	4	No		
2	Submersible Motor 1 HP,Submersible Pump 1 Hp Three Phase as per approval of Engineer In-Charge	1	No		
3	Inveter 1.5 Kw (Invt China) for Submersible	1	No		
4	Solar Mounting Frame Fixed	4	No		
5	Ac 4 Core Cable 4mm	100	Rft		
5	7/29 Cable For Panel Conections	100	Rft		
6	Safy Robe	50	Rft		
8	1" Dia PE Pipe PN12 (from Solar to Ground)	1000	Rft		
9	Acceseries (Fittings, Nuts & Bolts Supporting Girder)	1	Job		
10	Installation and comisioning Charges	1	Job		
11	Transportation	1	Job		
Sub Total (Pumping Machinery)					
Grand Total (1+2+3)					

Contractor Sign & Seal

10- Chautair 1, Ziarat

Type of Scheme: Rehabilitation of Drinking Water Facilities **Project:** Emergency Response for Snowfall/Flood Affectees at ziarat Balochistan

S.No	Description	Total Estimated Cost (Rs.)			
	1) Labour	Quantity/Nos	Unit	Unit Cost	Cost (Rs)
1	A) Skilled Labour	2	MD		
2	B. Unskilled	8	MD		
3	C. Plumber	1	Job		
Sub Total (Labour)					
	2) Materials				
1	Cement	11	No		
2	Sand	35	Cft		
3	Crash	71	Cft		
3	HDPE Pipe 2.5"	1200	Cft		
4	G.I Pipes 2"	10	Rft		
5	G.I Pipe 1.5"	10	Rft		
6	Transportation	1	Job		
7	Accessories (Fittings, cutting, jointi	1	Job		
9	G.I Bib Cock	15	No		
10	Sign Board	1	No		
Sub Total (Material)					
	3) Pumping Materials				
1	Electric 3Phase Submersible Motor 10HP with SP46-6Nos Router as per approval of Engineer In-Charge	1	No		
2	Ac 3 Core Cable 25mm	70	Rft		
3	Safy (Two Chain)	50	Rft		
4	2.5" Dia G.I Pipe (from Solar to Ground)	50	Rft		
5	Panel Board with Breakers	1	Job		
6	Accesseries (Fittings, Nuts & Bolts, Gate Valve, Cleag Pipes with Girder Support)	1	Job		
7	Installation and comisioning Charges	1	Job		
8	Transportation	1	Job		
Sub Total (Pumping Materials)					
Grand Total (1+2+3)					

Contractor Sign & Seal

11- Chautair 2, Ziarat

Type of Scheme: Rehabilitation of Drinking Water Facilities **Project:** Emergency Response for Snowfall/Flood Affectees at ziarat Balochistan

S.No	Description	Total Quoted Cost (Rs.)			
1) Labour		Quantity/Nos	Unit	Unit Cost	Cost (Rs)
1	A) Skilled Labour	5	MD		
2	B. Unskilled	13	MD		
3	C. Plumber	1	Job		
Sub Total (Labour)					
2) Materials					
1	Cement	24	No		
2	Sand	82	Cft		
3	Crash	164	Cft		
	HDPE 1" Pipe PN-12	2000	Rft		
4	G.I Pipes 2"	21	Rft		
5	G.I Pipe 1.5"	21	Rft		
6	Transportation	1	Job		
7	Accessories (Fittings, cutting, jointi	1	Job		
8	RCC Water Tank Construction (8'x6'x6')	1	Job		
9	G.I Bib Cock	24	No		
11	Sign Board	1	No		
Sub Total (Material)					
Grand Total (1+2)					

Contractor Sign & Seal

12-Shireen, Ziarat

Type of Scheme: Rehabilitation of Drinking Water Facilities **Project:** Emergency Response for Snowfall/Flood Affectees at ziarat Balochistan

S.No	Description	Total Quoted Cost (Rs.)			
	1) Labour	Quantity/Nos	Unit	Unit Cost	Cost (Rs)
1	A) Skilled Labour	2	MD		
2	B. Unskilled	8	MD		
3	C. Plumber	1	Job		
Sub Total (Labour)					
	2) Materials				
1	Cement	11	No		
2	Sand	35	Cft		
3	Crash	71	Cft		
4	G.I Pipes 2"	10	Rft		
5	G.I Pipe 1.5"	10	Rft		
6	Transportation	1	Job		
7	Accessories (Fittings, cutting, joint)	1	Job		
8	Water Tank	1	Job		
9	G.I Bib Cock	15	No		
10	Sign Board	1	No		
Sub Total (Material)					
	3) Pumping Machinery				
1	Electric 3Phase Submersible Motor 10HP with SP46-6 Nos Router as per approval of Engineer In-Charge	1	No		
2	Ac 3 Core Cable 25mm	70	Rft		
3	Safty (Two Chain)	50	Rft		
4	2.5" HDPE Pipe	1400	Rft		
5	Panel Board with Breakers	1	Job		
6	Accesseries (Fittings, Nuts & Bolts, Gate Valve, Cleag Pipes with Girder Support)	1	Job		
7	Installation and comisioning Charges	1	Job		
8	Transportation	1	Job		
Sub Total (Material)					
Grand Total (1+2+3)					

Contractor Sign & Seal

13-Gudda,Ziarat

Type of Scheme: Rehabilitation of Drinking Water Facilities **Project:** Emergency Response for Snowfall/Flood Affectees at ziarat Balochistan

S.No	Description	Total Quoted Cost (Rs.)			
		Quantity/Nos	Unit	Unit Cost	Cost (Rs)
1) Labour					
1	A) Skilled Labour	2	MD		
2	B. Unskilled	8	MD		
3	C. Plumber	1	Job		
Sub Total (Labour)					
2) Materials					
1	Cement	11	No		
2	Sand	35	Cft		
3	Crash	71	Cft		
4	G.I Pipes 2"	10	Rft		
5	G.I Pipe 1.5"	10	Rft		
6	Transportation	1	Job		
7	Accessories (Fittings, cutting, joint)	1	Job		
8	Water Tank	1	Job		
9	G.I Bib Cock	15	No		
10	Sign Board	1	No		
Sub Total (Material)					
2) Materials					
1	Electric 3Phase Submersible Motor 10HP with SP46-6Nos Routers as per approval of Engineer In-Charge	1	No		
2	Ac 3 Core Cable 25mm	70	Rft		
3	Safty (Two Chain)	50	Rft		
4	3" Dia G.I Pipe (from Solar to Ground)	1100	Rft		
5	Panel Board with Breakers	1	Job		
6	Accesseries (Fittings, Nuts & Bolts, 2 Gate Valve, Cleag Pipes with Girder Support)	1	Job		
7	Installation and comisioning Charges	1	Job		
8	Transportation	1	Job		
Sub Total (Material)					
Grand Total (1+2+3)					

Contractor Sign & Seal

14- Sparri Ghat, Ziarat

Type of Scheme: Rehabilitation of Drinking Water Facilities **Project:** Emergency Response for Snowfall/Flood Affectees at ziarat Balochistan

S.No	Description	Total Quoted Cost (Rs.)			
		Quantity/Nos	Unit	Unit Cost	Cost (Rs)
1) Labour					
1	A) Skilled Labour	3	MD		
2	B. Unskilled	18	MD		
3	C. Plumber	1	Job		
Sub Total (Labour)					
2) Materials					
1	Cement	16	No		
2	Sand	55	Cft		
3	Crash	110	Cft		
4	HDPE Pipe 2"	4800	Rft		
5	G.I Pipes 2"	10	Rft		
6	G.I Pipe 1.5"	10	Rft		
7	Transportation	1	Job		
8	Accessories (Fittings, cutting, jointi	1	Job		
9	Water Tank Repair	1	Job		
10	G.I Bib Cock	15	No		
11	Sign Board	1	No		
Sub Total (Material)					
Grand Total (1+2)					

Contractor Sign & Seal

15- Sakhobi, Ziarat

Type of Scheme: Rehabilitation of Drinking Water Facilities **Project:** Emergency Response for Snowfall/Flood Affectees at ziarat Balochistan

S.No	Description	Total Quoted Cost (Rs.)			
	1) Labour	Quantity/Nos	Unit	Unit Cost	Cost (Rs)
1	A) Skilled Labour	2	MD		
2	B. Unskilled	5	MD		
3	C. Plumber	1	Job		
Sub Total (Labour)					
	2) Materials				
1	Cement	8	No		
2	Sand	27	Cft		
3	Crash	55	Cft		
4	G.I Pipes 2"	10	Rft		
5	G.I Pipe 1.5"	10	Rft		
6	Transportation	1	Job		
7	Accessories (Fittings, 02 Gate Valve	1	Job		
8	Water Tank Repair with RCC Slab 1:2:4	1	Job		
9	G.I Bib Cock	15	No		
10	HDPE Pipe 2"	1000	Job		
11	HDPE 0.75" Pipe for Tapstands	100	Job		
12	Sign Board	1	No		
Sub Total (Material)					
Grand Total (1+2)					

Contractor Sign & Seal

16-Jangla Sir, Ziarat

Type of Scheme: Rehabilitation of Drinking Water Facilities **Project:** Emergency Response for Snowfall/Flood Affectees at ziarat Balochistan

S.No	Description	Total Estimated Cost (Rs.)			
		Quantity/Nos	Unit	Unit Cost	Cost (Rs)
1) Labour					
1	A) Skilled Labour	2	MD		
2	B. Unskilled	8	MD		
3	C. Plumber	1	Job		
Sub Total (Labour)					
2) Materials					
1	Cement	11	No		
2	Sand	35	Cft		
3	Crash	71	Cft		
4	G.I Pipes 2"	10	Rft		
5	G.I Pipe 1.5"	10	Rft		
6	Transportation	1	Job		
7	Accessories (Fittings, cutting, jointi	1	Job		
8	Water Tank	1	Job		
9	G.I Bib Cock	15	No		
10	Pumping Machinery	1	Job		
11	Sign Board	1	No		
Sub Total (Material)					
2) Materials					
1	Electric 3Phase Submersible Motor 10HP with SP46-6 Nos Router per approval of Engineer In-Charge	1	No		
2	Ac 3 Core Cable 25mm	70	Rft		
3	Safy (Two Chain)	50	Rft		
4	3" HDPE Pipe	1500	Rft		
5	Panel Board with Breakers	1	Job		
6	Accesseries (Fittings, Nuts & Bolts, Gate Valve, Cleag Pipes with Girder Support)	1	Job		
7	Installation and comisioning Charges	1	Job		
8	Transportation	1	Job		
Sub Total (Material)					
Grand Total (1+2+3)					

Contractor Sign & Seal

Summary Sheet of Wells

Sr.No	Village Name	Quoted Rates
1	Killi Sardaran	
2	Kill Baerh Chawtra	
3	Killi Gulzar Manan	
4	Killi Zarr China	
5	Killi Sheen Maghzai	
6	Killi Shadi Ghat	
7	Killi Chawtra	
8	Killi Wocha Ghoski	
9	Killi Badi Ghat	
10	Killi Chautair 1	
11	Killi Chautair 2	
12	Killi Shireen	
13	Killi Gudda	
14	Killi Spari Gatt	
15	Sakhobi	
16	Killi Jangla Sarr	
Grand Total (Inclusive of all Taxed and Profits)		