

Term & Conditions for the bidders.

Please read carefully the term and conditions before applying.

Instructions for Bidders.

1. Must be a registered firm with Government and FBR (Please attach copy of business Registration, NTN certificates).
2. Profile of the Firm with last 03 Years Experiences in WASH Sector with past 3 years Tax Returns files with Valid CNIC of the Owner/directors of the company.
3. Please attach last 06 Months bank statement of the Firm showing the financial strength.
4. Please attach bank soundness certificate of the firm.
5. Reference letters / Certificates showing the similar past experience with valid contact numbers.
6. No quotation will be acceptable for in-complete items in a specific kit.
7. All bids may be quoted on the basis of Unit Rate/item wise.
8. No mistake will be allowed in Unit Rate, in case of cutting and over writing the bidder should sign against the error with Stamp/Seal.
9. Muslim Hands have right to drop any item, if total cost of Toilets exceed the budget limit.
10. The Validity of the Quotation must be 60 days.
11. All the bids must contain the Date, legal name and address.
12. All bids must contain the earnest money @ 5% of the total bid in the shape of CDR/Bank Draft. Which will be returned either on rejection of bid / or (in case of awarding of tender), at the time of payment.
13. All bidders need to send two envelopes by courier, one for Technical Bid and 2nd for financial bid.
14. The quotation must include all applicable taxes which must be mentioned separately and if not mentioned than it will be considered including taxes.

Performance of the contract.

The performance of the contract will be in District Ziarat, at sites Ziarat City and Sanjavi as suggested in tender documents or as agreed upon.

Payment Method.

The payment will be made within 02 weeks (after deduction of all applicable taxes) after the Completion of all agreed work and having verification / Certificate of completion issued by the Interested firms submit their bids in sealed envelopes in the name of "Procurement Committee Muslim Hands", and the envelopes must mark as "Technical Bid" and "Financial Bid" applied for, not later than July 10th 2020 before 1400 hrs. The tenders will be opened on the same day.

Short listing.

The procurement committee will short list the bids on the basis of Earliest Completion of the Work, Lowest Bidder, Quality of Material, and Technical Evaluation of the vendor which will be communicated to the selected bidders in due course of time. Earliest Possible Work Completion will be counted and considered while bid analyses.

NOTE.

The Organization reserves the right to reject, cancel, negotiate, accept any offer without assigning any reason and without considering the lowest rate, or may divide one item/kit among more than 01 vendors.

The required specification of each kit is provided under. In case of any query related to specifications of kits etc., contact at (**Muslim Hands Regional Office, House # 48, New Algilani street,Zarghoon Road Quetta** or contact at **081-2869167** (hashimkhan_mhi@yahoo.com).

Cost Estimate for Construction of Toilets Block for Govt. Boys High School, Ziarat

A Twin Toilets (8 x7 & 8 X7)

S. No	Items & Specification	Quantity	Unit	Unit Rate	Amount
1	Excavation in foundation of building in all kind of soil including soft soil, hard rock, shingle/gravel etc. with back filling	194.29	Cft		
2	P/L Plain cement concrete including shuttering, placing, compacting, finishing and curing (nominal mix ration 1:4:8) in foundation under walls steps, floors etc. (the crush must be well graded, free from mud and dust and the sand will be fine & clear from mud/dust) as in foundation of main gate columns and coping on top of columns complete in all respect	69.10	Cft		
3	P/L Plain cement concrete including shuttering, placing, compacting, finishing and curing up to one week (nominal mix ration 1:2:4) in foundation under walls steps and slabs etc. (the crush must be well graded, free from mud and dust and the sand will be fine & clear from mud/dust) as in foundation of main gate columns and coping on top of columns complete in all respect.	77.28	Cft		
4	P/L Locally Available Stone Masonry in 1:4 cement sand mortar , comprising 9" and and above thick wall in foundation and above foundation including curing up to one week, masonry work must be good finished, Stones must be at least 9" Thick with uniform texture complete in all respects as in boundary walls and parapet walls .	68.35	Cft		

5	P/L First class burnt brick masonry in 1:4 cement sand mortar , comprising 9" and above thick wall in foundation and above foundation including curing up to one week, masonry work must be good finished, bricks must be 4.5" x 9" x 3" complete in all respects as in boundary walls and parapet walls .	135.30	Cft		
6	P/L Cement plaster in 1:3 CSM 1/2" in twin latrines set and Septic tank including curing, Shuttering complete in all respect	651.30	Sft		
7	P/L Reinforced cement concrete including shuttering, placing, compacting, finishing and curing up to two weeks (nominal mix ration 1:2:4) for slabs etc.	87.87	Cft		
8	Providing of jumbo size heavy duty plastic west bin with cover	2.00	No		
9	Providing and fixing steel made painted Handel's and hangar's for disable with nut, bolt for fixing on latrine wall for the support of old age and disables	6.00	No		
10	5 Hooks Stainless Steel Wall Hanger (دیوار گیر)	2.00	No		
11	Providing and Fixing glazed earthen ware WHB complete with all fittings, Size 22"x16": White with pedestal	2.00	No		
12	WC Indian Medium Size white color with flush Tank White	2.00	No		
13	WC English white color complete.	2.00	No		
14	Wash Hand Basin Medium (good quality white color) with basin mixer (stainless steel) including fittings and accessories complete in all respect.	2.00	No		
15	Air vent pipe PVC (2"dia x 10ft (PVC SCH 26/SDR 41)	20.00	Rft		
16	P-Trap (4" ceramic)	4.00	No		
17	PVC Elbow (4" Dia (UPVC))	16.00	No		

18	UPVC 4" Drainage pipe (PVC SCH 26/SDR 41)	60.00	Rft		
19	Solution for PVC pipes 125 Gm (transparent)	2.00	Can		
20	Floor Waste (Stainless steel 6"x6")	2.00	No		
21	Bibcock with wall flange (Good quality, corrosion resistive, excellent finish and durable)	4.00	No		
22	PPRC pipeline for sanitary work including cutting, jointing, testing, fitting complete in all respect (.75" dia)	91.00	Rft		
23	Providing and fixing PPRC Tee 0.75" dia	7.00	No		
24	Providing and fixing PPRC Reducer Tee 0.75" x 0.5" dia	6.00	No		
25	Providing and fixing PPRC Elbow 0.75" dia	10.00	No		
26	Providing and fixing GI Ball Valve 0.75" dia	2.00	No		
27	Providing and Installing CGI Sheet (Jasti Chadar) for Roof of Latrine including 1.5' Projection on each Side. All CGI Sheets are to be fixed on Ballies with necessary fittings including Nails, Cutting, bending etc. for the Roof of (20' x 11') Complete in all respect as per Satisfaction of Engineer In-Charge.	1.00	Job		
28	High Density Polyethylene Pipes (HDPE) For Water Supply PN12.5 of PE-100 Material including using of good quality thread seal Tape, fitting, jointing, testing & disinfect complete (0.75" dia)	200.00	Rft		
29	Manhole cover size (1'x1')	2.00	No		
30	Providing and fixing steel deformed round bars 1/2" dia Grade 60 main bars & distribution bars 7" c/c, including straightening, cutting, jointing and bending.	225.26	KG		
31	Iron Door (Pre-Painted Iron Oxide door of Size 3.5'x7' sheet SWG 20, with 1.25" Angel Iron frame and double diagonal bracing on back side SWG 14 approx. weight 20 kg, provided with handles and locking mechanism from both sides, with properly welded wire mesh ventilator built in door of height 1' on the top of door)	49.00	Sft		

32	Ventilators 2'x1' (Pre-Painted Iron Oxide side-hung ventilators which swing inward, have hinges, simple locking mechanism and sill operators and properly welded wire mesh on outer side)	2.00	No's		
33	Internal Electrification Complete with 2 Exhaust Fans, wire (7/29), Electric Boards, Energy Savers, Bulb Holders, Braker, main Board and all the necessary item required in Both Latrines as per Engineer's Directions	1.00	Job		
34	Providing and laying Three (3) coats of good quality distempering as in internal surface of Latrines & Three (3) coats of govt color weather shield as in external surface of Latrines, preparation of surface, arrangement of shuttering and good finishing complete.	651.30	Sft		
35	Prepare & Paint new surface, doors & windows Priming coat of Red Oxide and 2 coats of Paint	2.00	Jobs		
36	Providing and fixing Grab Bars Set (Types = suction cups Grab Bars, Wall to floor Grab Bars, angled Grab Bar and straight safety Grab Bars)	1.00	Set		
37	Providing and Fixing Stainless steel Handrail set, 3 ft Height as per Engineer guidance and supervision	25.00	Rft		
38	Water Tank made by CGI Sheet (Jasti Chadar) 18 SWG with size 4' x 4' x 4'	1.00	No		
	Total A				
B	Soakage Pit 3' internal dia				
S/No	Items & Specification	Quantity	Unit	Unit Rate	Amount

1	Excavation in foundation of Soakage pit in all kind of soil including soft soil, hard rock, shingle/gravel etc. with back filling	131.93	Cft		
2	P/L 2nd class burnt brick masonry in 1:5 cement sand mortar , comprising 4.5" and above thick wall in foundation and above foundation including curing up to one week, masonry work must be good finished, bricks must be 4.5" x 9" x 3" complete in all respects as in boundary walls and parapet walls .	18.89	Cft		
3	P/L Reinforced cement concrete including shuttering, placing, compacting, finishing and curing up to two weeks (nominal mix ration 1:2:4) in slabs etc.	3.97	Cft		
4	Providing and fixing steel deformed round bars 1/2" dia Grade 60, Main bars & distribution bars 6" c/c including straightening, cutting, jointing and bending.	13.74	KG		
5	P/L Stone ballast in soakage pit up to 3'	21.20	Cft		
	Total B				
C Sign Board / Visibility					
S/No	Items & Specification	Quantity	Unit	Unit Rate	Amount
1	Providing and installation of Sign Board size (4'X3') using 18 gauge steel sheet , IIL-M pipe 1.5" dia as in frame & foots with cross angel iron double strips of 1 feet length, writing of given data with ,MH & ECHO logo) and wall chalking on Latrine of the given data by Muslim Hands with logo complete.	1.00	Job		
	Total C				
	Net Total A+B+C				

Muslim Hands International

Cost Estimate for Construction of PWD & Women Friendly Toilets Block (for Girl's School Sanjavi)

A Twin Toilets (Block) Cost Estimation

S. No	Items & Specification	Quantity	Unit	Unit Rate	Amount
1	Excavation in foundation of building in all kind of soil including soft soil, hard rock, shingle/gravel etc. with back filling	194.29	Cft		
2	P/L Plain cement concrete including shuttering, placing, compacting, finishing and curing (nominal mix ration 1:4:8) in foundation under walls steps, floors etc. (the crush must be well graded, free from mud and dust and the sand will be fine & clear from mud/dust) as in foundation of main gate columns and coping on top of columns complete in all respect	69.10	Cft		
3	P/L Plain cement concrete including shuttering, placing, compacting, finishing and curing up to one week (nominal mix ration 1:2:4) in foundation under walls steps and slabs etc. (the crush must be well graded, free from mud and dust and the sand will be fine & clear from mud/dust) as in foundation of main gate columns and coping on top of columns complete in all respect.	77.28	Cft		

4	P/L Locally Available Stone Masonry in 1:4 cement sand mortar , comprising 9" and above thick wall in foundation and above foundation including curing up to one week, masonry work must be good finished, Stones must be at least 9" Thick with uniform texture complete in all respects as in boundary walls and parapet walls .	68.35	Cft		
5	P/L First class burnt brick masonry in 1:4 cement send mortar , comprising 9" and above thick wall in foundation and above foundation including curing up to one week, masonry work must be good finished, bricks must be 4.5" x 9" x 3" complete in all respects as in boundary walls and parapet walls .	135.30	Cft		
6	P/L Cement plaster in 1:3 CSM 1/2" in twin latrines set and Septic tank including curing, Shuttering complete in all respect	947.30	Sft		
7	P/L Reinforced cement concrete including shuttering, placing, compacting, finishing and curing up to two weeks (nominal mix ration 1:2:4) for slabs etc.	87.87	Cft		
8	Providing of jumbo size heavy duty plastic west bin with cover	2.00	No		
9	Providing and faxing steel made painted Handel's and hangar's for disable with nut, bolt for fixing on latrine wall for the support of old age and disables	6.00	No		
10	5 Hooks Stainless Steel Wall Hanger (دیوار گیر)	2.00	No		
11	Providing and Fixing glazed earthen ware WHB complete with all fittings, Size 22"x16": White with pedestal	2.00	No		
12	Triangle Bathroom Cabinet Toilet Corner Cabinet 90 Degree Corner Bathroom PVC	1.00	No		

13	WC Indian Medium Size white color with flush Tank White	2.00	No		
14	WC English white color complete.	2.00	No		
15	Wash Hand Basin Medium (good quality white color) with basin mixer (stainless steel) including fittings and accessories complete in all respect.	2.00	No		
16	Air vent pipe PVC (2"dia x 10ft (PVC SCH 26/SDR 41)	20.00	Rft		
17	P-Trap (4" ceramic)	4.00	No		
18	PVC Elbow (4" Dia (UPVC))	16.00	No		
19	UPVC 4" Drainage pipe (PVC SCH 26/SDR 41)	60.00	Rft		
20	Solution for PVC pipes 125 Gm (transparent)	2.00	Can		
21	Floor Waste (Stainless steel 6"x6")	2.00	No		
22	Bibcock with wall flange (Good quality, corrosion resistive, excellent finish and durable)	4.00	No		
23	PPRC pipeline for sanitary work including cutting, jointing, testing, fitting complete in all respect (.75" dia)	91.00	Rft		
24	Providing and fixing PPRC Tee 0.75" dia	7.00	No		
25	Providing and fixing PPRC Reducer Tee 0.75" x 0.5" dia	6.00	No		
26	Providing and fixing PPRC Elbow 0.75" dia	10.00	No		
27	Providing and fixing GI Ball Valve 0.75" dia	2.00	No		
28	Providing and Installing CGI Sheet (Jasti Chadar) for Roof of Latrine including 1.5' Projection on each Side. All CGI Sheets are to be fixed on Ballies with necessary fittings including Nails, Cutting, bending etc. for the Roof of (20' x 11') Complete in all respect as per Satisfaction of Engineer In-Charge.	1.00	Job		
29	High Density Polyethylene Pipes (HDPE) For Water Supply PN12.5 of PE-100 Material including using of good quality	200.00	Rft		

	thread seal Tape, fitting, jointing, testing & disinfect complete (0.75" dia)				
30	Manhole cover size (1'x1')	2.00	No		
31	Providing and fixing steel deformed round bars 1/2" dia Grade 60 main bars & distribution bars 7" c/c, including straightening, cutting, jointing and bending.	225.26	KG		
32	Iron Door (Pre-Painted Iron Oxide door of Size 3.5'x7' sheet SWG 20, with 1.25" Angel Iron frame and double diagonal bracing on back side SWG 14 approx. weight 20 kg, provided with handles and locking mechanism from both sides, with properly welded wire mesh ventilator built in door of height 1' on the top of door)	49.00	Sft		
33	Ventilators 2'x1' (Pre-Painted Iron Oxide side-hung ventilators which swing inward, have hinges, simple locking mechanism and sill operators and properly welded wire mesh on outer side)	2.00	No's		
34	Internal Electrification Complete with 2 Exhaust Fans, wire (7/29), Electric Boards, Energy Savers, Bulb Holders, Braker, main Board and all the necessary item required in Both Latrines as per Engineer's Directions	1.00	Job		
35	Providing and laying Three (3) coats of good quality distempering as in internal surface of Latrines & Three (3) coats of govt color weather shield as in external surface of Latrines, preparation of surface, arrangement of shuttering and good finishing complete.	947.30	Sft		
36	Prepare & Paint new surface, doors & windows Priming coat of Red Oxide and 2 coats of Paint	2.00	Jobs		

37	Providing and fixing Grab Bars Set (Types = suction cups Grab Bars, Wall to floor Grab Bars, angled Grab Bar and straight safety Grab Bars)	1.00	Set		
38	Providing and Fixing Stainless steel Handrail set, 3 ft Height as per Engineer guidance and supervision	25.00	Rft		
39	Water Tank made by CGI Sheet (Jasti Chadar) 18 SWG with size 4' x 4' x 4'	1.00	No		
40	MHM Kit Complete	1.00	No		
Total A					

B Soakage Pit 3' internal dia

S/No	Items & Specification	Quantity	Unit	Unit Rate	Amount
1	Excavation in foundation of Soakage pit in all kind of soil including soft soil, hard rock, shingle/gravel etc. with back filling	131.93	Cft		
2	P/L 2nd class burnt brick masonry in 1:5 cement sand mortar , comprising 4.5" and above thick wall in foundation and above foundation including curing up to one week, masonry work must be good finished, bricks must be 4.5" x 9" x 3" complete in all respects as in boundary walls and parapet walls .	18.89	Cft		
3	P/L Reinforced cement concrete including shuttering, placing, compacting, finishing and curing up to two weeks (nominal mix ration 1:2:4) in slabs etc.	3.97	Cft		

4	Providing and fixing steel deformed round bars 1/2" dia Grade 60, Main bars & distribution bars 6" c/c including straightening, cutting, jointing and bending.	13.74	KG		
5	P/L Stone ballast in soakage pit up to 3'	21.20	Cft		
Total B					
C Sign Board / Visibility					
S/No	Items & Specification	Quantity	Unit	Unit Rate	Amount
1	Providing and installation of Sign Board size (4'X3') using 18 gauge steel sheet , IIL-M pipe1.5" dia as in frame & foots with cross angel iron double strips of 1 feet length, writing of given data with ,MH & ECHO logo) and wall chalking on Latrine of the given data by Muslim Hands with logo complete.	1.00	Job		
Total C					
Net Total A+B+C					

Muslim Hands International

Cost Estimate for Construction of PWD & Women Friendly Toilets block RHC Sanjavi

A Twin Latrine (8' x 7' & 8' x 7')

S. No	Items & Specification	Quantity	Unit	Unit Rate	Amount
1	Excavation in foundation of building in all kind of soil including soft soil, hard rock, shingle/gravel etc. with back filling	224.48	Cft		
2	P/L Plain cement concrete including shuttering, placing, compacting, finishing and curing (nominal mix ration 1:4:8) in foundation under walls steps, floors etc. (the crush must be well graded, free from mud and dust and the sand will be fine & clear from mud/dust) as in foundation of main gate columns and coping on top of columns complete in all respect	73.41	Cft		
3	P/L Plain cement concrete including shuttering, placing, compacting, finishing and curing up to one week (nominal mix ration 1:2:4) in foundation under walls steps and slabs etc. (the crush must be well graded, free from mud and dust and the sand will be fine & clear from mud/dust) as in foundation of main gate columns and coping on top of columns complete in all respect.	77.28	Cft		

4	P/L Locally Available Stone Masonry in 1:4 cement sand mortar , comprising 9" and above thick wall in foundation and above foundation including curing up to one week, masonry work must be good finished, Stones must be at least 9" Thick with uniform texture complete in all respects as in boundary walls and parapet walls .	73.27	Cft		
5	P/L First class burnt brick masonry in 1:4 cement send mortar , comprising 9" and above thick wall in foundation and above foundation including curing up to one week, masonry work must be good finished, bricks must be 4.5" x 9" x 3" complete in all respects as in boundary walls and parapet walls .	141.72	Cft		
6	P/L Cement plaster in 1:3 CSM 1/2" in twin latrines set and Septic tank including curing, Shuttering complete in all respect	1,132.80	Sft		
7	P/L Reinforced cement concrete including shuttering, placing, compacting, finishing and curing up to two weeks (nominal mix ration 1:2:4) for slabs etc.	87.87	Cft		
8	Providing of jumbo size heavy duty plastic west bin with cover	2.00	No		
9	Providing and faxing steel made painted Handel's and hangar's for disable with nut, bolt for fixing on latrine wall for the support of old age and disables	6.00	No		
10	5 Hooks Stainless Steel Wall Hanger (دیوار گیر)	2.00	No		
11	Providing and Fixing glazed earthen ware WHB complete with all fittings, Size 22"x16": White with pedestal	2.00	No		
12	Triangle Bathroom Cabinet Toilet Corner Cabinet 90 Degree Corner Bathroom PVC	1.00	No		

13	WC Indian Medium Size white color with flush Tank White	2.00	No		
14	WC English white color complete.	2.00	No		
15	Wash Hand Basin Medium (good quality white color) with basin mixer (stainless steel) including fittings and accessories complete in all respect.	2.00	No		
16	Air vent pipe PVC (2"dia x 10ft (PVC SCH 26/SDR 41)	20.00	Rft		
17	P-Trap (4" ceramic)	4.00	No		
18	PVC Elbow (4" Dia (UPVC))	16.00	No		
19	UPVC 4" Drainage pipe (PVC SCH 26/SDR 41)	60.00	Rft		
20	Solution for PVC pipes 125 Gm (transparent)	2.00	Can		
21	Floor Waste (Stainless steel 6"x6")	2.00	No		
22	Bibcock with wall flange (Good quality, corrosion resistive, excellent finish and durable)	4.00	No		
23	PPRC pipeline for sanitary work including cutting, jointing, testing, fitting complete in all respect (.75" dia)	91.00	Rft		
24	Providing and fixing PPRC Tee 0.75" dia	7.00	No		
25	Providing and fixing PPRC Reducer Tee 0.75" x 0.5" dia	6.00	No		
26	Providing and fixing PPRC Elbow 0.75" dia	10.00	No		
27	Providing and fixing GI Ball Valve 0.75" dia	2.00	No		
28	Providing and Installing CGI Sheet (Jasti Chadar) for Roof of Latrine including 1.5' Projection on each Side. All CGI Sheets are to be fixed on Ballies with necessary fittings including Nails, Cutting, bending etc. for the Roof of (20' x 11') Complete in all respect as per Satisfaction of Engineer In-Charge.	1.00	Job		

29	High Density Polyethylene Pipes (HDPE) For Water Supply PN12.5 of PE-100 Material including using of good quality thread seal Tape, fitting, jointing, testing & disinfect complete (0.75" dia)	200.00	Rft		
30	Manhole cover size (1'x1')	2.00	No		
31	Providing and fixing steel deformed round bars 1/2" dia Grade 60 main bars & distribution bars 7" c/c, including straightening, cutting, jointing and bending.	225.26	KG		
32	Iron Door (Pre-Painted Iron Oxide door of Size 3.5'x7' sheet SWG 20, with 1.25" Angel Iron frame and double diagonal bracing on back side SWG 14 approx. weight 20 kg, provided with handles and locking mechanism from both sides, with properly welded wire mesh ventilator built in door of height 1' on the top of door)	49.00	Sft		
33	Ventilators 2'x1' (Pre-Painted Iron Oxide side-hung ventilators which swing inward, have hinges, simple locking mechanism and sill operators and properly welded wire mesh on outer side)	2.00	No's		
34	Internal Electrification Complete with 2 Exhaust Fans, wire (7/29), Electric Boards, Energy Savers, Bulb Holders, Braker, main Board and all the necessary item required in Both Latrines as per Engineer's Directions	1.00	Job		
35	Providing and laying Three (3) coats of good quality distempering as in internal surface of Latrines & Three (3) coats of govt color weather shield as in external surface of Latrines, preparation of surface, arrangement of shuttering and good finishing complete.	1,132.80	Sft		
36	Prepare & Paint new surface, doors & windows Priming coat of Red Oxide and 2 coats of Paint	2.00	Jobs		

37	Providing and fixing Grab Bars Set (Types = suction cups Grab Bars, Wall to floor Grab Bars, angled Grab Bar and straight safety Grab Bars)	1.00	Set		
38	Providing and Fixing Stainless steel Handrail set, 3 ft Height as per Engineer guidance and supervision	25.00	Rft		
39	Water Tank made by CGI Sheet (Jasti Chadar) 18 SWG with size 4' x 4' x 4'	1.00	No		
40	MHM Kit	1.00	No		
Total A					

B Soakage Pit 3' internal dia

S/No	Items & Specification	Quantity	Unit	Unit Rate	Amount
1	Excavation in foundation of Soakage pit in all kind of soil including soft soil, hard rock, shingle/gravel etc. with back filling	131.93	Cft		
2	P/L 2nd class burnt brick masonry in 1:5 cement send mortar , comprising 4.5" and above thick wall in foundation and above foundation including curing up to one week, masonry work must be good finished, bricks must be 4.5" x 9" x 3" complete in all respects as in boundary walls and parapet walls .	18.89	Cft		
3	P/L Reinforced cement concrete including shuttering, placing, compacting, finishing and curing up to two weeks (nominal mix ration 1:2:4) in slabs etc.	3.97	Cft		

4	Providing and fixing steel deformed round bars 1/2" dia Grade 60, Main bars & distribution bars 6" c/c including straightening, cutting, jointing and bending.	13.74	KG		
5	P/L Stone ballast in soakage pit up to 3'	21.20	Cft		
Total B					
C Sign Board / Visibility					
S/No	Items & Specification	Quantity	Unit	Unit Rate	Amount
1	Providing and installation of Sign Board size (4'X3') using 18 gauge steel sheet , ILL-M pipe1.5" dia as in frame & foots with cross angel iron double strips of 1 feet length, writing of given data with ,MH & ECHO logo) and wall chalking on Latrine of the given data by Muslim Hands with logo complete.	1.00	Job		
Total C					
Net Total A+B+C					